

# FEATURED JOB

## Heavy Duty Propping under 24 Tonne Footbridge



Alphasafe were asked to supply a temporary support for this footbridge as the retaining wall on the abutment had started bellowing out due to water content behind it. The Heavy Duty Allround props were used to take the load of the 24 tonne bridge off the abutment while the retaining wall was being rebuilt. The bridge needed to remain in use for foot traffic so the lateral propping was used to stop any side to side movement. The Heavy Duty Propping is remaining in place for up to 5 months as they repair the existing abutment and approach.

[Thanks to Mike and Ryan of Alphasafe for the photo.](#)

Please send us your photos, If you no longer wish to receive these Featured Jobs please contact us.

### LAYHER PTY LTD AUSTRALIA

Ph 1300 136 026

Fax 1300 136 027

[info@layher.com.au](mailto:info@layher.com.au)

[www.layher.com.au](http://www.layher.com.au)

PO Box R1353

Royal Exchange NSW 1225

Layher® 

More Possibilities. The Scaffolding System.

### LAYHER LTD NEW ZEALAND

Ph 0800 529 437

Fax 04 568 2788

[info@layher.co.nz](mailto:info@layher.co.nz)

[www.layher.co.nz](http://www.layher.co.nz)

PO Box 38388

Wellington Mail Centre 5045